Span(ft.)		Width(ft.)																			
	HT-70-46 (Standard Model)					HT-100-46				HT-120-46				HT-120-60				HT-140-60			
	4	5	6	7	8*	5	6	7	8*	5	6	7	8*	5	6	7	8*	5	6	7	8*
30	700	700	700	700*	700*																
40	700	700	700	600*	600*																
50	400	400	400/300*	300*	300*																
60	250	250	250/175*	175*	175*																
70	220	220	220/190*	175*	165*	500	500	500	500*												
80						400	400	400	400*												
90						350	350	350	250*	450	450	450/380*	380*								
100						175	160	150	150*	300	300	300/250*	250*								
110														250	250	250/180*	180*	500	500	500	500*
120														150	150	180/150*	100*	400	400	400	400*
130																		400	400	400	400*
140																		300	300	300	250*

- Designed in accordance with AISC Manual of Steel Construction, IBC, & ASCE standards.
- Constructed with ASTM A-500 Dual Grade B&C mill certified structural steel box tubing.
- Hot dipped galvanized, painted, powder coated, and GalvXtra rustic brown finishes available.
- Welded side panels to assist in reducing field installation time and labor.
- Full OSHA compliance.
- Custom widths and spans also available.
- Designed to meet all international building codes.
- Manufactured & containerized for exports.



